## **20t** TELESCOPIC SPREADER BEAM

শিল্যমান্ত্র





## ASSURANCE **SPECIFICATION** AS4991-2004 **Tare Weight:** 0.150t (Excl. slings/shackles) **Compliance Standard:** Yes Lifting lugs (top) suit: 17t Grade S bow shackle **Proof load tested:** Yes Load lugs (lower) suit: 12t Grade S bow shackle NDT Weld Inspection: Centre lug suits: 4.7t Grade S bow shackle Standard Finish\*: Painted (G36 Green) \*Other colours/finishes available on request

Span	WLL	(at includ	ed sling angle)		Approx. Sling Leg Length (Mtrs)			Approx.	Approx. Headroom (Mtrs)		
(Mtrs)	<b>60</b> °	<b>90</b> °	<b>120</b> °	CENTRE LIFT	60 °	<b>90</b> °	<b>120</b> °	<b>60</b> °	<b>90</b> °	<b>120</b> °	
2.65m	20t	16t	9t	3.5t	2.7	2.0	1.6	2.4	1.4	0.8	
3.1m	20t	16t	9t	3.0t	3.1	2.3	1.8	2.8	1.6	0.9	
3.55m	20t	16t	9t	2.6t	3.6	2.5	2.1	3.1	1.8	1.0	
4.0m	20t	16t	9t	2.3t	4.0	2.8	2.3	3.5	2.0	1.2	



