## 30t TELESCOPIC SPREADER BEAM





S	D	F	$\cap$	FI	CA	۸٦	ГΙ	n	N	ı
. つ	_	_				= 1		u	ıv	ш

Tare Weight:

0.200t (Excl. slings/shackles)

Lifting lugs (top) suit:

25t Grade S bow shackle

Load lugs (lower) suit:

17t Grade S bow shackle

Centre lug suits:

4.7t Grade S bow shackle

## **ASSURANCE**

Compliance Standard: AS4991-2004

Proof load tested: Yes

NDT Weld Inspection: Yes

Standard Finish\*: Painted (G36 Green)

\*Other colours/finishes available on request

Span	WLL (at included sling angle)				Approx. Sling Leg Length (Mtrs)			Approx. Headroom (Mtrs)		
(Mtrs)	60°	90°	120°	CENTRE LIFT	60°	90°	120°	60°	90°	120°
2.8m	30t	22t	12.5t	3.1t	2.8	2.0	1.6	2.4	1.4	0.8
3.2m	30t	22t	12.5t	2.8t	3.2	2.3	1.8	2.8	1.6	0.9
3.6m	30t	22t	12.5t	2.5t	3.6	2.5	2.1	3.1	1.8	1.0
4.0m	30t	22t	12.5t	2.2t	4.0	2.8	2.3	3.5	2.0	1.2

