50t TELESCOPIC SPREADER BEAM





MODEL
TSB1504

SPECIFICATION

Tare Weight:	0.260t (Excl. slings/shackles)					
Lifting lugs (top) suit:	35t Grade S bow shackle					
Load lugs (lower) suit:	25t Grade S bow shackle					
Centre lug suits:	6.5t Grade S bow shackle					

ASSURANCE

Compliance Standard:	AS4991-2004
Proof load tested:	Yes
NDT Weld Inspection:	Yes
Standard Finish*:	Painted (G36 Green)

*Other colours/finishes available on request

Span	WLL (at included sling angle)				Approx. S	Approx. Sling Leg Length (Mtrs)			Approx. Headroom (Mtrs)		
(Mtrs)	60°	90°	120 °	CENTRE LIFT	60°	90°	120 °	60°	90°	120°	
2.8m	50t	30t	18t	6t	2.8	2.0	1.6	2.4	1.4	0.8	
3.2m	50t	30t	18t	5.25t	3.2	2.3	1.8	2.8	1.6	0.9	
3.6m	50t	30t	18t	4.5t	3.6	2.5	2.1	3.1	1.8	1.0	
4.0m	50t	30t	18t	3.75t	4.0	2.8	2.3	3.5	2.0	1.2	



